

**BRUHATH BENGALURU MAHANAGARA PALIKE**  
**Yelahanka Division, Yelahanka Zone**

Executive Engineer  
 Yelahanka Division  
 B B M P Bengaluru - 54

No EE/YNK-D/E-PMT/08/2012-13 Dated: 13-12-2013

**APPROVED TENDER SCHEDULE - 'B'**

Item No: 50

Name of Work: -Construction of main culverts at COAL layout and Attur layout in Attur, ward no:03

| Sl | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Unit | Approved Qty | Rate Quoted by the Contractor<br>Approved Rates<br>Sri N Thirunagendra |                                         |
|----|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|--------------|------------------------------------------------------------------------|-----------------------------------------|
|    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |      |              | Rate                                                                   | Rate in Words                           |
| 1  | KSRRB 300-1 Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 Meters and an average lift upto 0.5m excavated surface leveled and sides neatly dressed the disposed earth to be levelled neatly after breaking of clods complete as per specifications and complete as per specifications with all lead and lift etc complete as per specification and direction of engineer incharge of the work.                                                                                           | Cum  | 200.71       | 65.00                                                                  | Rupees sixty five only                  |
| 2  | KSRRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 7.5 with OPC cement at 180kgs. with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation and finish, including cost of all materials, labour, 110M of machinery, curing complete as per specifications. Specification with all lead and lift complete as per specification as per direction of Engineer incharges | Cum  | 23.12        | 4200.00                                                                | Rupees four thousand two hundred only   |
| 3  | KSRRB 5.2-3:Providing and constructing granite / trap / basalt size stone masonry in foundation cement mortar 1:6 stone hammered dressed in courses not less than 20 cms high, bond stones at two m, apart in each course including cost of materials, labour, curing complete as per specifications.                                                                                                                                                                                                                                        | Cum  | 71.71        | 3500.00                                                                | Rupees three thousand five hundred only |
| 4  | Providing ruled pointing of coursed stone masonry with Cement mortar 1:3 20mm deep, after raking joints to depth of 20mm newly lining, including cost of materials, labour, 110M of machineries curing etc., complete as per specification and directions of the Engineer-in-charge                                                                                                                                                                                                                                                          | Sqm  | 119.52       | 75.00                                                                  | Rupees seventy five only                |

| SI | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | Unit    | Approved Qty | Rate Quoted by the Contractor<br>Approved Rates<br>Sr/N Thirunagendra |                                         |
|----|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------|--------------|-----------------------------------------------------------------------|-----------------------------------------|
|    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |         |              | Rate                                                                  | Rate in Words                           |
| 5  | KSRRB-4-1.6 : Providing and laying in position plain cement concrete of mix M 15 with 3% cement @ 240kgs, with 20mm and down size graded granitic metal coarse aggregates @0.878cum and fine aggregates @0.439cum machine mixed, concrete laid in layers not exceeding 15cm, thick, well compacted, in foundation and plinth, including cost of all materials, labour, H.O.M of machinery, curing complete as per specifications. Specification                                                                                                                                                                                                                                                                                                                                                                                                                                                             | Cum     | 22.43        | 4500.00                                                               | Rupees four thousand five hundred only  |
| 6  | KSRRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granitic metal coarse aggregates @0.878cum and fine aggregates @0.450cum with superplasticiser @ 315 conforming to IS9103-1999Refined machine mixed exceeding 15cm thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls/dary thickness) including attached plaster, columns, piers, abutments, pillars, posts, sills, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour H.O.M of machinery, curing, complete as per specifications. Specification with all lead and lift etc complete as per specification and direction of engineer incharge of the work. | Cum     | 38.11        | 5600.00                                                               | Rupees five thousand five hundred only  |
| 7  | KSRRB 4.9.2.providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, H.O.M of machinery complete as per specifications. Specification with all lead and lift etc complete as per specification and direction of engineer incharge of the work.                                                                                                                                                                                                                                                                                                                                                  | Quintal | 34.30        | 7500.00                                                               | Rupees seven thousand five hundred only |
| 8  | KSRRB 4.8.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, attached plaster, buttresses, buttresses plinth and string course including cost of all materials, labour complete as per specifications, with all lead and lift etc complete as per specification and direction of engineer incharge of the work.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Sqm     | 111.61       | 250.00                                                                | Rupees two hundred fifty only           |
| 9  | KSRRB M100-1 Loading and unloading of stone boulders/stone aggregates/sand/kankeer/morum, KSRRB M100-1:Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications. MORTH Chapter 1                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Cum     | 203.71       | 70.00                                                                 | Rupees seventy only                     |

Signature of the Contractor

Executive Engineer,  
Ayelabanka Division,  
BBMP, Bengaluru-64.